



Date
October 31, 2018

To
Prospective Bidder

Subject
Centerville-Washington Park District
Oak Grove Park Septic System

BID CLARIFICATION

The concrete floor sealer called for in the plans was not specified. The sealer needs to be a two-coat sealed concrete finish system – (1) primer/sealer epoxy coat – general polymers GP-3504, (1) polyurethane finish coat – General polymers GP-4638. Prepare concrete and install per manufacturers recommendations.

We just wanted to pass along the most up-to-date information regarding this specification.

If you have any questions, please contact our office.

Sincerely,



Brian J. Schmidt
Project Manager

West Central Ohio
440 E. Hoewisher Rd.
Sidney, OH 45365
937.497.0200 Phone

S. Ohio/N. Kentucky
203 W. Loveland Ave.
Loveland, OH 45140
513.239.8554 Phone

Eastern Indiana
607 N. Meridian St.
Portland, IN 47371
260.766.2500 Phone

