



Date

May 16, 2019

Subject

Village of Williamsburg
Gay Street Reconstruction Phase 1

Dear Prospective Bidder:

Enclosed please find Addendum No. 1 dated May 16, 2019.

Please acknowledge your receipt of this Addendum on page B-1, Article 3.01.A of your bid submittal.

If you have any questions, please contact us.

Sincerely,

A handwritten signature in purple ink that reads "Nicholas J. Selhorst".

Nicholas J. Selhorst
Project Manager

Enclosures: Addendum No. 1

West Central Ohio
440 E. Hoewisher Rd.
Sidney, OH 45365
937.497.0200 Phone

S. Ohio/N. Kentucky
203 W. Loveland Ave.
Loveland, OH 45140
513.239.8554 Phone

Eastern Indiana
607 N. Meridian St.
Portland, IN 47371
260.766.2500 Phone



Village of Williamsburg Gay Street Reconstruction Phase 1 Williamsburg, Ohio

May 16, 2019

ADDENDUM No. 1

Bidding Documents

Basis of Bid

Page B-6

The estimated quantities incorrectly stated C-909 for reference numbers 53, 54, and 55. They have been updated to show C-900 as the water main material.

Plan Sheets

General Notes and Estimated Quantities

Page 7

The estimated quantities incorrectly stated C-909 for reference numbers 53, 54, and 55. They have been updated to show C-900 as the water main material.

REF. NO.	ITEM NO.	DESCRIPTION	UNIT OF MEASURE	APPROX. QTY.	UNIT PRICE	TOTAL
52	630	SIGN DOUBLE FACED, STREET NAME	EACH	8		
53	638	4" AWWA C-900 DR-18 WATER MAIN, AS PER PLAN	FT.	24		
54	638	6" AWWA C-900 DR-18 WATER MAIN, AS PER PLAN	FT.	33		
55	638	8" AWWA C-900 DR-18 WATER MAIN, AS PER PLAN	FT.	1648		
56	638	8" INSERTING VALVE	EACH	1		
57	638	8" GATE VALVE	EACH	13		
58	638	3/4" TYPE "K" COPPER WATER SERVICE BRANCH, AS PER PLAN	FT.	500		
59	638	FIRE HYDRANT ASSEMBLY REMOVED	EACH	3		
60	638	6" FIRE HYDRANT ASSEMBLY, AS PER PLAN	EACH	3		
61	644	STOP LINE	FT.	189		
62	644	CROSSWALK LINE	FT.	784		
63	659	SEEDING AND MULCHING, CLASS 1, AS PER PLAN	S.Y.	1000		
64	832	STORM WATER POLLUTION PREVENTION PLAN	LUMP	1		
65	832	EROSION CONTROL	EACH	5000	\$1.00	\$5,000.00
CONSTRUCTION TOTAL						

Bidder acknowledges that (1) each Bid Unit Price includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, and (2) estimated quantities are not guaranteed, and are solely for the purpose of comparison of Bids, and final payment for all unit price Bid items will be based on actual quantities, determined as provided in the Contract Documents.

ITEM 638 6-INCH FIRE HYDRANT ASSEMBLY, AS PER PLAN

THIS ITEM OF WORK SHALL CONSIST OF THE WORK AS DESCRIBED IN OHIO DEPARTMENT OF TRANSPORTATION ITEM 638 WATER MAINS AND SERVICE BRANCHES, EXCEPT AS HEREIN MODIFIED.

THE ASSEMBLY WILL CONSIST OF THE FIRE HYDRANT, PIPE BRANCH, GATE VALVE WITH VALVE BOX, ANCHORING PIPE/COUPLING, ANCHORING TEE, AND BLOCKING,

PAYMENT FOR ITEM 638 6-INCH FIRE HYDRANT ASSEMBLY, AS PER PLAN, FOR ALL OPERATIONS DESCRIBED ABOVE SHALL BE AT THE CONTRACT EACH BID PRICE AND SHALL INCLUDE ALL LABOR, MATERIAL, AND EQUIPMENT REQUIRED TO COMPLETE THIS ITEM OF WORK.

ITEM 659 SEEDING AND MULCHING, CLASS 1, AS PER PLAN

THIS ITEM OF WORK SHALL CONSIST OF THE WORK AS DESCRIBED IN OHIO DEPARTMENT OF TRANSPORTATION ITEM 659, SEEDING AND MULCHING, EXCEPT AS HEREIN MODIFIED.

ALL AREAS DESIGNATED FOR SEEDING SHALL HAVE A MINIMUM OF 6" OF TOPSOIL OVER THE ENTIRE AREA. TESTING THE PH OF ANY EXISTING OR IMPORTED TOPSOIL PER ODOT 659.02 SHALL BE WAIVED. THE AREA SHALL BE HAND-RAKED AND DRESSED READY FOR SEEDING. NO STONE OVER 1" IN SIZE PERMITTED IN THE TOP 6".

SEEDING AND MULCHING SHALL BE APPLIED TO ALL AREAS OF EXPOSED SOIL. QUANTITY CALCULATIONS FOR SEEDING AND MULCHING ARE BASED ON PROJECT WORK LIMITS.

IT'S THE CONTRACTOR'S SOLE RESPONSIBILITY TO PROVIDE THE REQUIRED GERMINATION RATES AND ENSURE THE GRASS IS ESTABLISHED TO THE SATISFACTION OF THE VILLAGE WHICH MAY REQUIRE WATERING, REGRADING/ADDING TOPSOIL AND RESEEDING.

ANY AREAS THAT HAVE ERODED OR WHERE NEW GRASS DID NOT GERMINATE SHALL BE ADDRESSED BY THE CONTRACTOR UNTIL THE AREAS ARE STABILIZED, SHAPED, AND DRAINED, AS INDICATED IN THE PLANS.

ANY DISTURBED AREA, OUTSIDE OF THE PROJECT WORK LIMITS, CAUSED BY THE CONTRACTOR'S WORK, SHALL BE RESTORED TO THE SATISFACTION OF THE PROPERTY OWNER AND VILLAGE, AT THE CONTRACTOR'S SOLE EXPENSE.

THIS ITEM INCLUDES: TOPSOIL, SEEDING, MULCHING, COMMERCIAL FERTILIZER, WATER, AND REPAIR SEEDING AND MULCHING.

PAYMENT FOR ITEM 659 SEEDING AND MULCHING, CLASS 1, AS PER PLAN, FOR ALL ABOVE OPERATIONS, SHALL BE AT THE CONTRACT SQUARE YARD BID PRICE AND SHALL INCLUDE ALL LABOR, MATERIAL, AND EQUIPMENT REQUIRED TO COMPLETE THIS ITEM OF WORK.


ESTIMATED QUANTITIES 

REF. NO.	ITEM NO.	DESCRIPTION	UNIT OF MEASURE	APPROX. QTY.
1	201	CLEARING AND GRUBBING	LUMP	1
2	202	REMOVED, AS PER PLAN	LUMP	1
3	202	PIPE REMOVED, 24" AND UNDER	FT.	2677
4	202	WALL REMOVED AND RELOCATED	S.F.	52
5	202	WALK REMOVED	S.F.	13063
6	202	CURB REMOVED	FT.	581
7	202	FENCE REMOVED AND RESET	FT.	64
8	202	CATCH BASIN REMOVED	EACH	15
9	202	MANHOLE REMOVED	EACH	2
10	202	VALVE BOX REMOVED	EACH	5
11	203	EXCAVATION INCLUDING EMBANKMENT CONSTRUCTION, AS PER PLAN	C.Y.	3006
12	204	SUBGRADE COMPACTION	S.Y.	6026
13	204	EXCAVATION OF SUBGRADE, AS PER PLAN	C.Y.	1004
14	301	ASPHALT CONCRETE BASE, PG. 64-22	C.Y.	446
15	304	AGGREGATE BASE, AS PER PLAN	C.Y.	1016
16	407	NON-TRACKING TACK COAT, (APPLIED AT 0.06 GAL./S.Y.)	GAL.	318
17	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448)	C.Y.	254
18	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448) PG64-22	C.Y.	186
19	452	6" NON-REINFORCED CONCRETE PAVEMENT, AS PER PLAN	S.Y.	264
20	605	4" SHALLOW PIPE UNDERDRAIN, (707.31) (PERFORATED), AS PER PLAN	FT.	600
21	608	ODOT CONCRETE STEPS, TYPE B	FT.	2
22	608	4" CONCRETE WALK	S.F.	12060
23	608	CURB RAMP	S.F.	916
24	609	CLERMONT COUNTY STANDARD ROLL CURB	FT.	2771
25	611	4" CONDUIT, TYPE B, 707.45, STORM REPAIR	FT.	100
26	611	6" CONDUIT, TYPE B, 707.45, STORM REPAIR	FT.	100
27	611	8" CONDUIT, TYPE B, 707.45, STORM REPAIR	FT.	100
28	611	6" STORM SEWER, AS PER PLAN	FT.	248
29	611	12" STORM SEWER, AS PER PLAN	FT.	289
30	611	15" STORM SEWER, AS PER PLAN	FT.	52
31	611	18" STORM SEWER, AS PER PLAN	FT.	39
32	611	24" STORM SEWER, AS PER PLAN	FT.	722
33	611	30" STORM SEWER, AS PER PLAN	FT.	740
34	611	STORM CLEANOUT, AS PER PLAN	EACH	3
35	611	TYPE 2-2B CATCH BASIN, AS PER PLAN	EACH	1
36	611	TYPE 2-3 CATCH BASIN, AS PER PLAN	EACH	1
37	611	TYPE 1 CATCH BASIN, AS PER PLAN	EACH	18
38	611	TYPE 3 STORM SEWER MANHOLE, AS PER PLAN	EACH	8
39	611	CLEANOUT ADJUSTED TO GRADE	EACH	1
40	611	6" SANITARY SEWER LATERAL, AS PER PLAN	FT.	554
41	611	8" PVC SDR-35 SANITARY SEWER, AS PER PLAN	FT.	1154
42	611	TYPE 3, SANITARY SEWER MANHOLE, AS PER PLAN	EACH	5
43	611	TYPE D, SANITARY DROP MANHOLE, AS PER PLAN	EACH	1
44	611	6" SANITARY SEWER LATERAL REPAIR	FT.	100
45	614	MAINTAINING TRAFFIC	LUMP	1
46	623	CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN	LUMP	1
47	630	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	EACH	1
48	630	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	EACH	22
49	630	REMOVAL OF GROUND MOUNTED POST AND DISPOSAL	EACH	18
50	630	GROUND MOUNTED SUPPOT, NO. 3 POST	FT.	242
51	630	SIGN, FLAT SHEET	S.F.	93
52	630	SIGN DOUBLE FACED, STREET NAME	EACH	8
53	638	4" AWWA C-900 DR-18 WATER MAIN, AS PER PLAN	FT.	24
54	638	6" AWWA C-900 DR-18 WATER MAIN, AS PER PLAN	FT.	33
55	638	8" AWWA C-900 DR-18 WATER MAIN, AS PER PLAN	FT.	1648
56	638	8" INSERTING VALVE	EACH	1
57	638	8" GATE VALVE	EACH	13
58	638	3/4" TYPE "K" COPPER WATER SERVICE BRANCH, AS PER PLAN	FT.	500
59	638	FIRE HYDRANT ASSEMBLY REMOVED	EACH	3
60	638	6" FIRE HYDRANT ASSEMBLY, AS PER PLAN	EACH	3
61	644	STOP LINE	FT.	189
62	644	CROSSWALK LINE	FT.	784
63	659	SEEDING AND MULCHING, CLASS 1, AS PER PLAN	S.Y.	1000
64	832	STORM WATER POLLUTION PREVENTION PLAN	LUMP	1
65	832	EROSION CONTROL	EACH	5000



SIDNEY, OHIO 937.497.0000
 LOVELAND, OHIO 513.239.8554
 PORTLAND, INDIANA 760.766.2500
 WWW.CHOICEONEENGINEERING.COM

**GAY STREET RECONSTRUCTION PHASE 1
 VILLAGE OF WILLIAMSBURG
 GENERAL NOTES AND ESTIMATED QUANTITIES**

REVISIONS:
 ADDENDUM #1
 5-16-19

FILE NAME
 GNC

DRAWN BY
 WJW

CHECKED BY
 NNS

PROJECT No.
 CLEWL1702

DATE
 05-02-2019

SHEET NUMBER