

TO 1	FIG. 1	and the second
RIA	Tabu	lation
-		

Centerville Washington Park District
Bill Yeck Parking Lot

Bill Yeck Parking Lot August 26, 2021 Brumbaugh Construction Oakley Blacktop
Arcanum, Ohio Dayton, Ohio

Double Jay Construction, Inc. Englewood, Ohio Outdoor Enterprise Troy, Ohio

		. rigii leerii ig			Aug	ust 26, 2021		Arcanum, Omo		Dayton, Onio		Lingic wood, Oillo		1109, 01110
REF.	ITEM		UNIT OF	APPROX.	UNIT	TOTAL	UNIT	TOTAL	UNIT	TOTAL	UNIT	TOTAL	UNIT	TOTAL
NO.	NO.	DESCRIPTION	MEASURE	QTY.	<u>COST</u>	COST	COST	<u>COST</u>	COST	<u>COST</u>	<u>COST</u>	COST	<u>COST</u>	COST
1	201	CLEARING AND GRUBBING, AS PER PLAN	LUMP	1	\$10,000.00	\$10,000.00	\$5,000.00	\$5,000.00	\$9,500.00	\$9,500.00	\$6,200.90	\$6,200.90	\$12,000.00	\$12,000.00
2	202	REMOVED, AS PER PLAN	LUMP	1	\$8,500.00	\$8,500.00	\$12,059.00	\$12,059.00	\$6,500.00	\$6,500.00	\$5,700.00	\$5,700.00	\$8,300.00	\$8,300.00
3	202	WALK REMOVED	S.F.	89	\$8.00	\$712.00	\$3.00	\$267.00	\$10.00	\$890.00	\$2.00	\$178.00	\$2.00	\$178.00
4	202	PAVEMENT REMOVED	S.Y.	36	\$25.00	\$900.00	\$20.00	\$720.00	\$10.00	\$360.00	\$63.50	\$2,286.00	\$12.00	\$432.00
5	203	EXCAVATION, INCLUDING EMBANKMENT CONSTRUCTION, AS PER PLAN	C.Y.	369	\$20.00	\$7,380.00	\$20.00	\$7,380.00	\$35.00	\$12,915.00	\$18.60	\$6,863.40	\$25.00	\$9,225.00
6	204	SUBGRADE COMPACTION AND PROOF ROLLING, AS PER PLAN	S.Y.	1108	\$2.00	\$2,216.00	\$1.00	\$1,108.00	\$1.00	\$1,108.00	\$1.50	\$1,662.00	\$1.00	\$1,108.00
7	204	EXCAVATION OF SUBGRADE, AS PER PLAN	C.Y.	60	\$50.00	\$3,000.00	\$50.00	\$3,000.00	\$50.00	\$3,000.00	\$59.50	\$3,570.00	\$5.00	\$300.00
8	254	1-1/2"± PAVEMENT PLANING, ASPHALT CONCRETE	S.Y.	782	\$7.00	\$5,474.00	\$9.50	\$7,429.00	\$6.50	\$5,083.00	\$10.50	\$8,211.00	\$10.00	\$7,820.00
9	304	AGGREGATE BASE, LIMESTONE, AS PER PLAN	C.Y.	246	\$40.00	\$9,840.00	\$55.00	\$13,530.00	\$55.00	\$13,530.00	\$58.00	\$14,268.00	\$65.00	\$15,990.00
10	407	NON-TRACKING TACK COAT, 0.09 GAL/S.Y.	GAL.	170	\$4.50	\$765.00	\$5.00	\$850.00	\$10.00	\$1,700.00	\$5.85	\$994.50	\$5.00	\$850.00
11	441	2-1/2" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448)	C.Y.	77	\$200.00	\$15,400.00	\$200.00	\$15,400.00	\$190.00	\$14,630.00 *1	\$222.65	\$17,144.05	\$210.00	\$16,170.00
12	441	1-1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG 64-22	C.Y.	79	\$190.00	\$15,010.00	\$215.00	\$16,985.00	\$210.00	\$16,590.00	\$234.35	\$18,513.65	\$220.00	\$17,380.00
13	623	CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN	LUMP	1	\$2,750.00	\$2,750.00	\$2,000.00	\$2,000.00	\$1,800.00	\$1,800.00	\$2,636.50	\$2,636.50	\$5,000.00	\$5,000.00
14	630	GROUND MOUNTED SUPPORT, NO. 3 POST	EACH	1	\$500.00	\$500.00	\$60.00	\$60.00	\$250.00	\$250.00	\$193.35	\$193.35	\$200.00	\$200.00
15	630	SIGN, FLAT SHEET	EACH	1	\$250.00	\$250.00	\$60.00	\$60.00	\$200.00	\$200.00	\$181.65	\$181.65	\$200.00	\$200.00
16	630	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	EACH	2	\$250.00	\$500.00	\$100.00	\$200.00	\$250.00	\$500.00	\$143.55	\$287.10	\$60.00	\$120.00
17	642	HANDICAP SYMBOL MARKING	EACH	1	\$250.00	\$250.00	\$75.00	\$75.00	\$45.00	\$45.00	\$76.20	\$76.20	\$75.00	\$75.00
18	642	PARKING LOT STALL MARKINGS	FT.	460	\$5.00	\$2,300.00	\$1.00	\$460.00	\$1.00	\$460.00	\$0.75	\$345.00	\$1.00	\$460.00
19	642	STOP LINE	FT.	38	\$10.00	\$380.00	\$2.50	\$95.00	\$2.00	\$76.00	\$2.90	\$110.20	\$3.00	\$114.00
20	642	CHANNELIZING LINE, 8"	FT.	40	\$10.00	\$400.00	\$1.50	\$60.00	\$1.00	\$40.00	\$1.75	\$70.00	\$2.00	\$80.00
21	642	LANE ARROW	EACH	6	\$250.00	\$1,500.00	\$40.00	\$240.00	\$25.00	\$150.00	\$41.00	\$246.00	\$40.00	\$240.00
22	642	TRANSVERSE/DIAGONAL LINES	FT.	798	\$5.00	\$3,990.00	\$1.00	\$798.00	\$0.50	\$399.00	\$1.00	\$798.00	\$1.00	\$798.00
23	659	SEEDING AND MULCHING, AS PER PLAN	S.Y.	515	\$3.00	\$1,545.00	\$5.00	\$2,575.00	\$6.00	\$3,090.00 *2	\$10.50	\$5,407.50	\$9.00	\$4,635.00
24	661	DECIDUOUS TREE, 2" RED MAPLE, AS PER PLAN	EACH	4	\$500.00	\$2,000.00	\$300.00	\$1,200.00	\$650.00	\$2,600.00	\$377.50	\$1,510.00	\$1,000.00	\$4,000.00
25	SPEC	PARKING BLOCK	EACH	25	\$140.00	\$3,500.00	\$100.00	\$2,500.00	\$125.00	\$3,125.00	\$87.00	\$2,175.00	\$85.00	\$2,125.00
		TOTAL			_	\$99,062.00		\$94,051.00	_	\$98,541.00 *3	_	\$99,628.00		\$107,800.00
					=		_		_		=		_	

^{*1} Total given was \$14,360.00

^{*2} Total given was \$3,030.00

^{*3} Total given was \$98,211.00